



REPUBLIC OF THE PHILIPPINES
NATIONAL IRRIGATION ADMINISTRATION
 QUEZON IRRIGATION MANAGEMENT OFFICE

May 12, 2022

The Manager
G.R. BERNALES CONSTRUCTION & SUPPLIES
 Taal Street De Mesa Compound
 Brgy. Gulang-Gulang, Lucena City, Quezon

NOTICE TO PROCEED

Ma'am:


Notice is hereby given that you can proceed with the **Project Identification No: 4AQ-VAR-19-043** for the **Construction of River Protection, Pump House, Pipe Laying & Procurement, Delivery & Installation of Solar Pump of Anawan Small Irrigation Project in Polillo, Quezon right after receipt hereof in accordance with terms and conditions of the Agreement, General Conditions, Instruction to Bidders, Plans and Technical Specifications of the item of works specified below:**

ITEMS OF WORKS	QUANTITY	UNIT COST	TOTAL COST
I. PUMP WORKS			
200 GPM AT 28 METERS TDH, CENTRIFUGAL PUMP, CAST IRON VOLUTE AND BRONZE FITTED, WITH MECHANICAL SEAL, SIZE 2 INCHES X 1.5 INCHES, SUCTION AND DISCHARGED COUPLED TO 3HP, 3PHASE, 60HZ, 1800 RPM, 230V/440AC, MOUNTED IN A COMMON BASE WITH	1.00 l.s.	840,000.00	840,000.00
1 COUPLING AND COUPLING GUARD			
PROC., DELIVERY AND INSTALLATION OF 2" DIA. HDPE	8.00 pcs.	2,000.00	16,000.00
2 PIPE SDR21 (P.N. 6.3) PE100			
3 PUMP HOUSE	1.00 l.s.	278,000.00	278,000.00
4 CLASS "A" CONCRETE ORDINARY	3.71 cu.m.	16,560.00	61,437.60
5 CLASS "A" CONCRETE RETAINING WALL	3.96 cu.m.	18,217.00	72,139.32
6 RUBBLE MASONRY	3.70 cu.m.	9,125.90	33,765.83
7 STRUCTURE EXCAVATION (MANUAL)	20.00 cu.m.	219.00	4,380.00
8 STRUCTURE BACKFILL W/ COMPACTION (MANUAL)	14.00 cu.m.	233.00	3,262.00
9 COFFERDAMMING	4.00 cu.m.	341.00	1,364.00
10 DEWATERING	151.90 cu.m.	208.00	31,595.20
11 2" DIA. G.I. FOOT VALVE	1.00 pcs.	5,680.00	5,680.00
12 2" DIA. CHECK VALVE	1.00 pcs.	6,850.00	6,850.00
13 2" DIA. X 45 DEG. HDPE ELBOW	2.00 pcs.	850.00	1,700.00
14 COUPLING REDUCER 1.5 X 2 INCHES	1.00 pcs.	1,870.00	1,870.00
15 TRASH RACK	51.35 kgs.	73.25	3,761.39
II. CANAL SYSTEM			
1 CLASS "A" CONCRETE ORDINARY	3.88 cu.m.	16,560.00	64,252.80
PROC., DELIVERY AND INSTALLATION OF 4" DIA. HDPE	53.00 cu.m.	4,600.00	243,800.00
2 PIPE SDR21 (P.N. 6.3) PE100			
3 4" DIA. GATE VALVE	1.00 cu.m.	25,000.00	25,000.00
4 SAND BEDDIG	9.53 cu.m.	3,313.00	31,572.89
5 STRUCTURE EXCAVATION (MANUAL)	51.00 cu.m.	219.00	11,169.00
6 STRUCTURE BACKFILL W/ COMPACTION (MANUAL)	53.00 pcs.	233.00	12,349.00
7 4" DIA. X 2" DIA. HDPE TEE REDUCER	1.00 cu.m.	2,500.00	2,500.00
8 2" DIA. GATE VALVE	1.00 cu.m.	17,200.00	17,200.00
9 2" DIA. X 90 DEG. ELBOW	2.00 pcs.	1,400.00	2,800.00
TOTAL			₱ 1,772,449.03

In this condition, you are advised to submit to the Office for approval a complete construction program for the orderly performance of the Contract Works, showing in detail the proposed program operation for each item of work including the use of equipment right after receiving this notice.

Please acknowledge receipt hereof.

Very truly yours,


EDWIN C. NAZARENO
 Acting Division Manager

Received by:

Cc: The Regional Manager
 NIA Region IV-A
 Pila, Laguna




 Gerielyn R. Bernales

