



REPUBLIC OF THE PHILIPPINES
NATIONAL IRRIGATION ADMINISTRATION
QUEZON IRRIGATION MANAGEMENT OFFICE

May 05, 2022

The Manager
M.C. REFAZO BUILDERS
Dahlia St. Villa Aurea Subdivision
Brgy. Domoit, Lucena City, Quezon

NOTICE TO PROCEED

Ma'am:


Notice is hereby given that you can proceed with the **Contract No: 4AQ-CRP-22-003** for the **Procurement, Delivery and Installation of Submersible Solar Pump, Construction of Canal Structures and Pipe Laying of Caldong Small Irrigation Project** in Sampaloc, Quezon right after receipt hereof in accordance with terms and conditions of the Agreement, General Conditions, Instruction to Bidders, Plans and Technical Specifications of the item of works specified below:

ITEMS OF WORKS	QUANTITY	UNIT COST	TOTAL COST
I. Pump Works			
1 Class "A" Concrete Retaining Wall	4.58 cu.m.	15,797.10	72,350.72
2 Class "A" Concrete Ordinary Diversion Works	1.55 cu.m.	14,322.20	22,199.41
3 2.50m x 2.50m Control Room	1.00 lot	108,750.00	108,750.00
4 Submersible solar pump with 19HP and 22kw Solar Inverter, 6" dia. Discharge Pipe Capable of Delivering 600 GPM x 24 meter TDH	1.00 lot	1,844,500.00	1,844,500.00
5 6" dia. x 60 deg Elbow	2.00 pcs.	3,200.00	6,400.00
6 6" dia. x 45 deg Elbow	1.00 pc.	3,200.00	3,200.00
7 6" dia. Check Valve	1.00 pc.	13,500.00	13,500.00
8 6" dia. x 90 deg Elbow	2.00 pcs.	3,200.00	6,400.00
9 6" dia. GI Pipe	7.00 pcs.	17,442.90	122,100.30
10 Common Excavation	11.00 cu.m.	165.00	1,815.00
11 Common Backfill	4.50 cu.m.	137.50	618.75
12 Dewatering	94.50 cu.m.	222.50	21,026.25
13 Cofferdamming	6.50 cu.m.	316.30	2,055.95
14 4" dia. x 7hp Pump and Engine and Accessories	1.00 lot	48,567.90	48,567.90
II. Canal Structures			
1 Class "A" Concrete Ordinary	3.12 cu.m.	14,322.20	44,685.26
2 4" dia. HDPE Pipe	26.00 pcs.	3,342.00	86,892.00
3 2" dia. HDPE Pipe	94.00 pcs.	960.00	90,240.00
4 4" dia. Gate Valve	2.00 pcs.	9,092.00	18,184.00
5 2" dia. Gate Valve	5.00 pcs.	4,592.00	22,960.00
6 Sand Bedding	29.60 cu.m.	2,665.00	78,884.00
7 Common Excavation	118.40 cu.m.	165.00	19,536.00
8 Common Backfill	118.40 cu.m.	137.50	16,280.00
III. CONSTRUCTION SAFETY AND HEALTH PROGRAM (CHSP)	1.00 lot	35,000.00	35,000.00
TOTAL			P 2,686,145.54

In this condition, you are advised to submit to the Office for approval a complete construction program for the orderly performance of the Contract Works, showing in detail the proposed program operation for each item of work including the use of equipment right after receiving this notice.

Please acknowledge receipt hereof.

Very truly yours,


EDWIN C. NAZARENO
Acting Division Manager

Cc: The Regional Manager
NIA Region IV-A
Pila, Laguna

Genes Aguilar Street, Brgy. 10, Lucena City, Quezon, Philippines
Tel. Nos.: (042) 710 3470 Telefax No.: (042) 710 2422
Website: region4a.nia.gov.ph • Facebook: www.facebook.com/region4a.nia.gov.ph
TIN: 000916415039

